City of Norfolk

Small Lot SWPPP for Individual Lots Less than 1 Acre Not to Scale


The contractor shall reduce pollution, erosion and sediment leaving the construction site by implementing Best Management Practices (BMPs) such as:

- Limit mud track-out into streets by parking on paved surfaces whenever possible. If necessary use temporary rock drive or construct concrete driveway early on during construction.
- Clean up any mud tracked off of construction site in a timely manner.
- Implement sediment controls along the lower sides of the property to protect adjacent water ways, storm drains, public ROW and neighboring property from sedimentation.
- Keep a clean site. Dispose of construction waste materials and debris in a dumpster or containment device. Store all hazardous materials indoors.
- Portable toilet must be staked and anchored away from any storm drain inlets.
- Inspect your site bi-weekly and after rain events to find any potential problems and keep your Best Management Practices repaired and in good working order.
- 7. Maintain vegetation buffer where possible around the perimeter of the site.
- 8. A plastic lined concrete washout pit should be maintained and used until all concrete work is complete.
- 9. Place stock piled soil behind sediment control measures.

For more information on erosion and sediment control BMPs, contact the City of Norfolk, 402-844-2020.

Instructions to complete Small Lot SWPPP

- Indicate North Arrow.
- 2. Draw in drainage arrows demonstrating the direction of runoff.
- Draw in location of needed sediment control and identify type of proposed sediment control (silt fence, wattles, etc.)
- Draw in location of proposed access during construction and identify the surfacing material proposed during construction (concrete, crushed rock).
- 5. Identify location of soil stockpiles and ensure sediment control is installed around stockpile.
- Identify location of plastic lined concrete washout pit. If trucks are to washout offsite then identify location of washout.
- 7. Identify the final stabilization method (sod/seed) and proposed time line.
- 8. Identify any other BMP's necessary to prevent erosion, trackout, pollution or sediment from leaving the site.
- 9. Complete the information below.



Disclaimer: The City of Norfolk incurs no liability for the use or misuse of this Small Lot SWPPP.

\LAR\typical-siteplan.dwg